












Regulatory Speed Limit	50 km/h	60 km/h	70 km/h	80 km/h	90-100 km/h
1a Taper Length For Lane Closure	35 (1:10)	55 (1:15)	75 (1:20)	90 (1:25)	110 (1:30)
1b Taper Length For Shoulder Work on Where TCPs Used (Min. 3 Cones)	5	8	10	12	15
2 Maximum Distance Between Cones or Tubular Markers for 1a	10	10	10	10	10
3 Minimum Tangent Distance Between Tapers	30	60	90	120	150
4 Distance Between Construction Signs	40	60	80	100	150

**LEGENDS:**

-  SIGN STAND
-  DELINEATORS
-  TCP
-  ARROWBOARD TRUCK
-  POLE
-  REMOVE POLE
-  MANHOLE/SERVICE BOX
-  NEW AERIAL CABLE
-  NEW U/G CABLE


**Scope:**  
 - Repair lateral guard for Pole 1


**Dates:**  
 - January 19 – February 2, 2018

**Hours:**  
 - 7:00am – 5:00pm

**Drawing #:**  
 - 46387 Chilliwack Central Road

**Notes:**  
 - All traffic control devices and signs to comply with Latest MOTH Manual Work on Roadway





**COMPANY:** DIXON NETWORKS CORPORATION

**CONTACT:** WILLIAM WONG  
**PHONE:** 604-940-8817 EXT. 240

**DIXON**  
 NETWORKS CORPORATION