

Date: Plan developed Oct 15, 2022 Author: JoAnn Isaac Project: KGH Equipment

Comments:

Work will be performed with single lane alternating and signed accordingly to Figure 7.8 from the MOTI Manual for Work on Roadways.

1 TCP will be utilized in the middle to relay to TCP's on the end when traffic is leaving the side road and give the all clear for sending in each direction.

Tapers will need to be changed when the work crew performs work on the east side of the roadway.

Shorter sections may be done and signs moved closer to work zone on those dates.



Manifest

- 42 x Cone
- 3 x C-027
- 3 x Flagger
- 2 x C-018-1A
- 2 x C-030-8
- 2 x Sign
- 1 x Titlebox

